Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.

Schedule - B

Name of the Work : Improvemets to drain at 1st, 2nd, 3rd and 4th Cross Vishveshwaraiah at Bagalagunte in ward no. 14.

SNo	Item Name	Unit	Estimate Quantity	Rate to be Quoted M/s M/s Sri. Shivakumar. BH	
				In Figures (Rs)	In Words (Rs)
1	KSRRB 300-1 : Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH /Chapter 3 (Page No.142, Item No. 19.1)	Cum	288.90	91.70	Rupees Ninety One and Seventy Paisa Only
2	Removing B.S slab of Drain and stacking and Removing & Refixing stone slabs of drains and pointing in C.M (1:3) (Page No.25, Item No. 5.32 & 5.33)	Sqm	252.72	154.33	Rupees One Hundred Fifty Four and Thirty Three Paisa Only
3	KSRB 4 - 1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (Page No.12, Item No. 4.3)	Cum	64.53	5442.77	Rupees Five Thousand Four Hundred Fourty Two and Seventy Seven Paisa Only
4	Providing a granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete for 7.5 cms thick (Page No.25, Item No. 5.31.1)	Sqm	1010.88	702.29	Rupees Seven Hundred and Two and Twenty Nine Paisa Only
5	Providing a granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete for 10 cms thick (Page No.25, Item No. 5.31.2)	Sqm	442.80	871.16	Rupees Eight Hundred Seventy One and Sixteen Paisa Only
6	KSRB 5-8.2: Providing two line dressing to granite stone slab/granite stone masonry as per specification. KBS 5.1.13 (Page No.24, Item No. 5.18)	Sqm	442.80	1016.53	Rupees One Thousand and Sixteen and Fifty Thiree Paisa Only
7	Providing Edge machine cutting to Granite slabs as per specification and direction of engineer in charge of the work.	Rmtr	2460.00	63.30	Rupees Sixty Three and Thirty Paisa Only

Shivakumar
gnature of Contractor

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Pa
Dasarahalli Division, Bangalo
Executive Engineer

Scanned by CamScanner

8	KSRB 5.3-3 : Providing and constructing granite / trap/ basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing, complete as per specifications.KBS 5.1.13 (Page No.23, Item No. 5.9)	Cum	4.05	5597.09	Rupees Five Thousand Five Hundred Ninety Seven and Nine Paisa Only
9	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation plinth and cills including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (Page No.13, Item No. 4.7)	Cum	70.74	5906.86	Rupees Five Thousand Nine Hundred and Six and Eighty Six Paisa Only
10	KSRB 5-14.1 : Providing and construction load bearing wall with solid concrete block of Size 400x200x200mm having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1) : 2005 and constructed CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges scaffolding, curing, hire charges of machineries etc., Complete as specification(Page No.25, Item No. 5.27.1)	Sqm	748.80	1047.85	Rupees One Thousand and Fourty Seven and Eighty Five Paisa Only
11	Supplying and fixing precast reinforced conceret slabs 10cm thick of mix M20 using 20mm and sownsize graded grantite metal using reinforecement 100mm dia steel at 150mm C/C both ways cost, transportation, hire charges of machinerym machine cuttng the vertical face to get plain even surface etc., complete with all lead and lift conveyance charges, labour charges inclusive of cost of all materials	Sqm	399.60	1791.39	Rupees One Thousand Seven Hundred Ninty One and Thirty Nine Paisa Only
12	Providing & fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 200mm & down size with steel reinforcement including formwork, lift charges, curing & concrete finished surface both sides etc,. And as per drawing & the direction of Engineer-in-charge (Data Rate approved)	Sqm	9.00	5026.02	Rupees Five Thousand and Twenty Six and Two Paisa Only
13	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450 x 200 x 400 mm (Page No.25, Item No. 5.29.1)	No.s	2080.00	407.06	Rupees Four Hundred and Seven and Six Paisa Only

Shivakumar
Signature of Contractor

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike,
Basavanahalli Division, Bangalore-560
Executive Engineer

Scanned by CamScanner

14	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. (Page No.122, Item No.15.80)	Sqm	421.20	29.08	Rupees Twenty Nine and Eight Paisa Only
15	KSRB 15-19.2 : Providing and applying spary painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materiasl, labour, complete as per specifications. (Page No.122, Item No.15.81)	Sqm	421.20	73.81	Rupees Seventy Three and Eighty One Paisa Only
16	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4KM a) Basic rate for haulage of materials as per item No. 17.4/ KSRRB: M100-4,1 ... Rs. 2.00 Tonne / Km b) Average earth of work 1.28 Tonne / Km Rs, 2.00 c) Add loading and unloading Page. No. 133 Item No. 17.1 PWD SR 2016-17	Cum	288.90	90.36	Rupees Ninty and Thirty Six Paisa Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division

Shivakumar
gnature of Contractor

Executive Engineer

Scanned by CamScanner